r	Star,	1 1	<u> </u>				1017	375		
MA	R 2 4 1992 20	O I	ENGINE	RING DATA	[RANSN	IITTAL	1. EDT	1235	Page 1	of
2. To:	(Receiving Organization)			3. From: (Originat	ıng Organiz	ation)	4. Relat	ed EDT No);	
	rojects and			Canadan	- 0		N/A		<u>.</u>	
ט	istribution			Geosciences	s Group		7. Purch	ase Order	No:	
5. Pro)/Prog/Dept/Div: W=017H			6. Cog/Proj Engr:	B. A. 1	Villiams		/Compon	ant No:	
8. Ori	ginator Remarks:					1	N/A	усотпрот	ent NO:	
F	or review and appr	oval of O	dex Tes	t Plan			10. Syste	em/Bldg/F	acility:	
				AFTE	CVE	DFOR	N/A			
				•			-1	or Assm D	wg No:	
11. R€	eceiver Remarks:			7. K	ille	LEASE nd 3/23/92	N/A		A A = 12	
					acen		N/A	mit/Permi	т Арриса	tion ivo.
							 	uired Resp	onse Dat	:e:
15.		DA [.]	TA TRANS	MITTED			(F)	(G)	(H)	(1)
(A)	(B) Document/Drawing No.	(C) Sheet	(D) Rev No.	(E) Title or De	scription of	Data Transmitted	Impact Level	Reason for	Origi- nator	Receiv- er
No.							1	Trans- mittal	Dispo- sition	Dispo- sition
1	WHC-SD-EN-TP-009		11/A	Odex Test Pl	an		3	1		
			0;8			8780				
	,	```			343	7077				
		_		, ,	(No. 10)	125				
<i>r</i> :			 		S M	CELLE 55	 			
V					27 V	3)				
44-24					التقا	, & V				
16.				KEY	Se CE P	252721206	· · · · · · · · · · · · · · · · · · ·			
	Impact Level (F)		Reason fo	or Transmittal (G)		Di	sposition (H) & (I)		
	, 2, 3, or 4 see MRP 5.43 and EP-1.7	1. Approval 2. Release	4. Rev 5. Pos	riew st-Review		Approved Approved w/comme	ent 5. F	Reviewed Reviewed	w/commi	ent
		3. Information		t (Receipt Acknow. Re		3. Disapproved w/com	ment 6. F	Receipt ac	knowled	ged
(G)	(H) 17.			IGNATURE/DIST					(G)	(H)
Rea- son	Disp (J) Name	(K) Signature	(L) Date	(L) NISM (M)	Name	(K) Signature (L) Date	(M) MSIN	Rea	, ,
1	Cog./Proj. Eng B.	A. Willia	ams Z	all 12-7-	EL	MC (2)		14-22	3	
1	1 Cog./Proj. Eng. Mgr.	K. R. F	echt /	C(9-+3/1412		M CLEARANCE	Н	4-17	3	
1		ckaberry	Sill Flore	Jefrey 3442						
<u> </u>	Safety D. Hes	Invital	- Fless	10 Har 92						
	J. Dorian f. J. Dorian	Mr Maline	1	3-10-92					- 	
	J. J. Jakast	WIT THE STEAM	2031mi	-//						
18.		19.		20/	1/2/12	11/	21. DOE	┷ ┷ ┷ ┷ ┷ ┷ ┷ ┷ む む む む む む む む む む む む	L (if requ	red)
K.	D. Reynolds 3/10/42	_		K	R. Fe	cht 3/10/92		Approved		
	ture of EDT Date	Authorized	Represent		nizant/Proj gineer's Mar			Approved Disapprov		
O light	W.VI	101 Vecelal	g Vryamz	Eng	jures a ividi	·uye·				

THIS PAGE INTENTIONALLY
LEFT BLANK

INFORMATION RELEASE REQUEST WHC-CM-3-4 COMPLETE FOR ALL TYPES OF RELEASE Purpose New ID Number Speech or Presentation [] Reference 71WHC-SD-EN-TP-009, Rev. 0 [x] Technical Report (Check [] Full Paper Existing ID Number (include revision, volume, etc.) only one Thesis or Dissertation [] Summary suffix) [] Manual Abstract (1 Brochure/Flier If previously cleared, list ID number Visuai Aid E3 Software/Database [3 Speakers Bureau [] Controlled Database Date Release Required Poster Session [] Other [] Videotape 3/23/93 Title Unclassified Category Impact 3 ODEX TEST PLAN Level UC-COMPLETE FOR SPEECH OR PRESENTATION Title of Journal Group or Society Sponsoring NA NA Date(s) of Conference or Meeting City/State Will proceedings be published? Yes No NA Will material be handed out? Yes No Title of Conference or Meeting NA CHECKLIST FOR SIGNATORIES Review Required per WHC-CM-3-4 Yes No Reviewer Name (printed) Signature <u>Date</u> Classification/Unclassified Controlled TX1 Nuclear Information Patent - General Counsel [X]5W BERGUN Legal - General Counsel [X]D. WILLIAMSON Applied Technology/Export Controlled Information or International Program, $[\cdot]$ [X]WHC Program TXI Communications .[] DOE-RL Program П [X] **Publication Services** [X]Ε. SMITH Other Program ٢1 [X] References Available to Intended Audience B. A. [X]WILLIAMS Transmit to DOE-HQ/Office of Scientific and Technical Information [X]Information conforms to all applicable requirements. The above information is certified to be correct. Author/Requestor (Printed/Signature) Date INFORMATION RELEASE ADMINISTRATION APPROVAL STAMP B. A. WILLIAMS Stamp is required before release. Release is contingent upon resolution of mandatory comments. 3/17/97 Responsible Manager (Printed/Signature)

Date Received

Intended Audience

Internal

Sponsor

External

THIS PAGE INTENTIONALLY

SUPPORTING DOCUMENT	. [1, 10]	1. Total Pages <u>45</u>	
2. Title Odex Test Plan	3. Number WHC-SD-EN-TP-009	4. Rev. No.	
5. KeyWords Drilling technology, evaluation of Odex alternatives	6. Author B. A. Williams Name (Type or Print) Signature Geosciences Group Organization/Charge Code	N 81331/	

7. Abstract

The Odex Test Plan will evaluate the ability to drill State compliant groundwater monitoring wells at Hanford. Objectives and test criteria outlined in this plan provide the guidelines for meeting the requirements for well installations.

APTHOVED FOR
PUBLIC RELEASE

1. Birkland 3/23/92

8. PURPOSE AND USE OF DOCUMENT. This document was prepared for use within the U.S. Department of Energy and its contractors. It is to be used only to perform, birect, or integrate work under U.S. Department of Energy contracts. This document is not approved for public release until reviewed.

PATENT STATUS - This document copy, since it is transmitted in advance of patent clearance, is made available in confidence solely for use in performance of work under contracts with the U.S. Department of borgy. This document is not to be published nor its contents otherwise disseminated or used for purposes other than specified above before patent approval for such release or use has been secured, upon request, from the U.S. Department of Energy, Patent Attorney, Richland Operations Office, Richland, WA

DISCLAIMER – This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

9. Impact Level

3

U.		<u>ĸ.</u>	recnt
	Autho	rize	d Manager's Name (Type or Print)
(Δ	<u>C</u> C	Cat-
`	Autho	rıze	d Manager's Signature
	Specif	y Dis	stribution Limit

RELEASE STAMP

OFFICIAL RELEASE
BY WHO ED TO DATE MAR 2 4 1992

Star. 21

THIS PAGE INTENTIONALLY LEFT BLANK

WHC-SD-EN-TP-009, Rev. 0

CONTENTS

1.0	INTRODUCTION
2.0	OBJECTIVES
3.0	SCOPE
4.0	DESCRIPTION OF TEST 4.1 TEST ITEM 4.2 TEST LOCATION
5.0	EXPECTED RESULTS
6.0	TEST PROCEDURE
7.0	SAFETY
8.0	QUALITY ASSURANCE
9.0	ORGANIZATION AND FUNCTION RESPONSIBILITIES
10.0	SCHEDULE
11.0	REPORTS
12.0	DATA SHEETS
13.0	REFERENCES
APPE	ENDICES
A B C D	ODEX Test Documentation
FIGU	URES
1 2	Hanford Site Map
3 4	and 299-W6-12

9 2

This page intentionally left blank.

...... ______

5.48

9 0

1.0 INTRODUCTION

This plan is an instruction for the investigation and data requirements necessary to evaluate the usefulness and applicability of utilizing Odex drilling methods to construct compliant groundwater monitoring wells on the Hanford Site.

2.0 OBJECTIVES

The objective of the test is to demonstrate improvement in the economic efficiencies of installing Resource Conservation and Recovery Act (RCRA) compliant groundwater monitoring wells with quality maintained. Specifically, this test will evaluate: (1) efficiency and cost effectiveness, and (2) the ability to obtain quality site characterization data during well construction.

3.0 SCOPE

Odex drilling will be evaluated by installing a minimum of three CY 1992 RCRA groundwater monitoring wells. This equipment will be supplied and maintained by the construction contractor for the demonstration. The project engineer will provide direction to the contractor to proceed with the test when all applicable documentation, site preparation, and equipment is in place as outlined in the latest revision of the *Generic Well Specification* (WHC 1991).

4.0 DESCRIPTION OF TEST

4.1 TEST ITEM

In

N

0

The test is designed to evaluate the applicability and efficiency of the Odex drilling system for the construction of RCRA groundwater monitoring wells. The Odex is an air-circulating, top-drive rotary drilling method with a downhole air hammer and rotary percussion bit assembly. The system allows the wellbore to be cased simultaneously with drilling. The test evaluation will include:

- The ability of the Odex drilling method to drill and install RCRA compliance wells
- Comparison of drilling time of Odex vs. 1991 Kaiser Engineers Hanford (KEH) RCRA drilling time
- Comparison on manpower support requirements of Odex vs. 1991 KEH RCRA drilling
- Comparison of the relative development times and volumes of water produced for an Odex wells vs 1991 KEH RCRA wells.

4.2 TEST LOCATION

The test will take place at a minimum of three locations on the Hanford Site (see Figure 1). Two wells, 299-W6-11 and 299-W6-12, are located at the north end of Waste Management Area 5 of the Low-Level Burial Grounds in 200 West Area. The third well, 299-E35-44, is south of the Grout Treatment Facility, which is directly east of 200 East Area (see Figures 2 and 3). The expected stratigraphic sequence for the test wells in 200 West Area is listed below in descending order:

- Hanford Formation
 - mixed gravel (open framework) and sand unit
- Ringold Formation
 - early Palouse/Plio-Pleistocene-calcic silty sandy unit
 - partially indurated pebble to cobble gravel unit
 - quartzo-feldspathic sand and silt unit

The expected stratigraphic sequence for the test well just outside 200 East Area is listed below in descending order:

- Hanford Formation
 - basaltic sand unit
 - pebble to cobble gravel (open framework)
- Ringold Formation
 - partially indurated gravel unit

The assessment of geologic and chemical data from wells adjacent to the test locations, as well as available groundwater data, indicate that there is no radiologic or hazardous waste contamination present in the vicinity of the test locations.

Additional testing of the Odex system at other locations on the Hanford Site will be considered.

4.3 EQUIPMENT

1 /2

 $\langle \cdot \cdot \cdot \rangle$

S

9

The equipment necessary for the completion of this test will be as follows:

- Odex tools, top-drive rotary rig and air supply system
- Cyclones and drill cutting containment system
- Penetration rate and downtime chart recorder (see Appendix A)
- · Other equipment normally onsite to support drilling activities.

4.4 DATA COLLECTION AND EVALUATION

Data for evaluating the performance criteria (listed in Section 4.5) will be compiled from penetration rate logs, Daily Field Activity Reports, geological and geophysical logs as per Environmental Investigation Instruction (EII) (WHC 1988) and Generic Well Specification (WHC 1991). The 200 West Area was chosen as the test location for two wells. It is known as a difficult area for drilling and casing extraction, and will present a significant test of the Odex capabilities. Maximum penetration rates will be evaluated at the test location in the 200 East Area, which is known to contain a thick sand interval.

The potential for drilling through lost circulation zones will be tested in open framework gravels. During drilling, samples will be collected continuously in a sample tube located under the sample cyclone (Figure 4). Cuttings will be examined and preserved in 5-ft increments as per specifications. The drilling system will also be tested for the ability to drive and retrieve a split tube or other sampler for exact lithologic characterization. A minimum of one split spoon will be taken in each test well. Comparison of cutting descriptions, penetration rates, and geophysical logs will be correlated with adjacent wells to determine if relevant geologic/hydrologic criteria have been observed.

Data for evaluating average drilling rates will be compiled from penetration and downtime records, and Daily Field Activity Reports. This data will be compared with KEH activities during the installation of RCRA groundwater monitoring CY 1991 wells.

Data for evaluating manpower support will be gathered by tracking the number of personnel working on location, as recorded on the Daily Field Activity Reports. This data will compare with KEH RCRA 1991 activities.

Data to evaluate well development will be documented on the Daily Field Activity Reports and the Well Development Form. This data will be compared with time and volume comparisons for cable tool well development.

4.5 TEST PLAN CRITERIA/CONSTRAINTS

Listed below are the performance criteria that will determine the ability to drill and construct RCRA groundwater monitoring wells with Odex. The evaluation will be based on these criteria and by comparing Odex and cable tool results. The cable tool data will be from CY 1991 RCRA drilling.

- Ability to physically penetrate Hanford Site formations with minimum disturbance to in-situ soils (e.g., minimize overproducing cuttings)
- Ability to penetrate at an acceptable drilling rate
- Ability to construct well to desired depth/diameter and to install standard RCRA well components and assemblies
- · Ability not to over drill more than 2 ft below design depth

- Ability to segregate perched water or contaminated intervals by sealing and/or downsizing casing (e.g., to prevent cross contamination between aquifers)
- Ability to identify lithologies of all formations
- Ability to obtain representative sediment samples to determine physical and chemical soil hydrogeological parameters (e.g., grain size distribution, water content, calcium carbonate content, and possibly sediment contamination) at intervals of 5 ft or at changes in lithology
- Ability to perform geophysical logging

riji.

tar les

S

0

- · Ability to contain formation fluid and drill cuttings
- Ability to minimize fluid losses and gains to and from the formation
- Ability to prevent potential contaminants entrained in the compressor air from contaminating the groundwater and soil
- Ability to measure water levels during drilling
- · Ability to remove all temporary casing and shoes.

For the purpose of this test all pertinent and relevant governing documents and regulations will be followed. Applicable documents relevant to the field testing of the Odex are given in Section 13.0.

5.0 EXPECTED RESULTS

Success of the four categories outlined in Section 4.1 will be determined by evaluation of drilling performance as outlined in Section 4.5. Each category will be evaluated based on the ability to satisfy current operating and performance standards, and governing regulations. The results from the Odex evaluation will be compared with cable tool performance. The baseline for cable tool performance will be determined from 1991 KEH RCRA drilling. Recommendations on the applicability of utilizing Odex at the Hanford Site will be outlined with the final evaluation.

6.0 TEST PROCEDURE

The test comprises drilling and completing a minimum of three RCRA wells with the Odex drilling system. The test will be performed under existing guidelines as outlined in Section 4.0. Field records will provide the data for evaluation of the test performance criteria. Drilling will be conducted by the contractor and all field activities and pertinent documentation will be overseen by Westinghouse Hanford Company (Westinghouse Hanford) personnel.

7.0 SAFETY

Overall site safety is addressed by the site specific safety plans for the areas in which the wells will be drilled. The safety evaluation and requirements for the Drill Cutting Containment System has been addressed previously (WHC 1990 and Appendix B). In addition, the Odex system test has been addressed and approved by Westinghouse Hanford Safety as shown in Appendix C. For the purposes of safety all test personnel will have stop work authority for safety and operational concerns.

8.0 QUALITY ASSURANCE

Quality assurance shall be in accordance with the *Project Specific Quality Assurance Plan for Groundwater Monitoring Wells* (WHC 1989). Kaiser Engineers Hanford Company shall implement and operate to the provisions specified in *Kaiser Engineers Hanford Generic Quality Assurance Program Plan for Drilling Construction Activities* (KEH 1991).

9.0 ORGANIZATION AND FUNCTION RESPONSIBILITIES

Organizations responsible for implementation of this test drilling activity are as follows:

- Westinghouse Hanford Projects—The Project Engineer is responsible for project logistics, daily drilling and technical operation decisions relative to KEH and the drilling subcontractor
- Westinghouse Hanford Geosciences Group—The RCRA Cognizant Engineer and RCRA Field Geologist are responsible to enforce documentation per WHC (1991) of activities on the appropriate forms, as outlined by WHC (1988), and technical decisions concerning drilling requirements relevant to RCRA compliant wells
- Westinghouse Hanford Health Physics is responsible for site radiation monitoring
- KEH is responsible for implantation of the subcontract for the Odex Drilling Company, the Site Specific Safety Plan and the Site Safety Officers
- Jensen Drilling is responsible for fulfilling the subcontract commitments to KEH/Westinghouse Hanford.

10.0 SCHEDULE

See Appendix D.

11.0 REPORTS

A final report evaluating the four main areas of testing and the conclusions derived from the evaluation will be prepared as per the schedule (see Appendix D).

12.0 DATA SHEETS

All data for documentation of the test will be recorded on the following documents: (see Appendix A)

- · Daily Field Activity Report
- Borehole Log

10

E.354, 340


 \sim

0

- Well Development Form
- Penetration Rate Chart/Downtime Chart-Geologic Strip Chart
- Drill Log/Rig Activity Sheet
- Well Summary Sheet
- Well Construction Report
- Geophysical Logs.

13.0 REFERENCES

- KEH, 1991, Kaiser Engineers Hanford Generic Quality Assurance Program Plan for Drilling Construction Activities, No. 27, Rev. 9
- WHC, 1988, Environmental Investigations and Site Characterization Manual, WHC-CM-7-7, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1989, Project Specific Quality Assurance Plan for Groundwater Monitoring Wells, WHC-SD-WM-QAPP-002, Rev. 1, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1990, Results of Testing the Dual Wall Percussion Hammer Method and Drill Cuttings Containment System at the Hanford Site, WHC-SD-WM-TRP-042, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1991, Generic Well Specification, WHC-S-014, Rev. 6, Westinghouse Hanford Company, Richland, Washington.



Hanford Site Map.

GEOSCI\ 110890-8




Figure 2. Locations of Low-Level Burial Ground Wells 299-W6-11 and 299-W6-12.




Figure 3. Location of Grout Facility Well Number 299-E25-44.




Figure 4. Cyclone and Cutting Containment System.

APPENDIX A ODEX TEST DOCUMENTATION

ហ

N

0

Section 1. Section 1.

2123740156

O`

THIS PAGE INTENTIONALLY LEFT BLANK

			FIE		/ITY REPOR TOOL RIG	RT –				Page	2 <u>1</u> of
Date	We	li No	Rig	Model	Rig No	Cont	ractWor	k Order No.	Start Card No)	Report No
Purpose			L	····	-l	l.,		Reference		Locat	ion
Casing Siz	ze	Set At	Туре	Shoe Size	Casing Start (Depth	Casing	End Depth	Start Ti	me	
					Depth Starte	д	Depth	Ended	ŀ		····
eference	e/Measur	ing Point				1	Total SI Footag	hift e	Contractor Ti	me _	
1aterials	Used				Contra	act Line	items	 , · · · · · · · · · · · · · · · · · · ·	Personnel		·····
									Operator	me (Ac	Lic No ceptance)
									Other:		ecptance,
							- 		o and .		
Dep (fee	oth et)	Ordling Method									
From	То	HT DB			C	Descrip	tion of O	perations/Re	marks		
		ST	1						· · · · · · · · · · · · · · · · · · ·		
		<u> </u>		·							
							· •				
		 		···-						'	
	· · · · · · · · · · · · · · · · · · ·								··········		
							· · · · · · · · · · · · · · · · · · ·				
							·*·				


									·		·····
				·							.
									· · · · · · · · · · · · · · · · · · ·		
				·	<u> </u>	····			- <u> - - - - - - - - - </u>		·
Report By	у					Revi	ewed By				
itle		·				Title				Da	ste
ignature	e					Signa	ture				

Distribution: White - Group File Custodian Yellow - Group Files Pink - Project Coordinator Goldenrod - Team Leader BC-6000-290 (02/90)

WHC-SD-EN-TP-009, Rev. 0 DRILL LOG / RIG ACTIVITY REPORT SHEET 2

PROJECT or W.O.	NO	SUBC	CONTRAC	CT NO	coi	MPUTER NO	D	SHIFT:	
DATE: W	ELL NO	RIG	NO	LOCATION	:	_ DRILLER:	:		
START DEPTH:	END	DEPTH:_		FOOTAGE:	R	I.O.P	DAYS	on WELL: _	
CURRENT ACTIVIT									
CURRENT BIT [:=====	======:		±======	CE282221
				SER. NO		TYPE:		NEW/RE	RUN
				TG. RUN:					
BIT CHANGE[]									
BIT SIZE	: N	IFG		SER. NO		TYPE: _		NEW/RE	RUN
BIT IN	: B	IT OUT:	F	TG. RUN:	R.0	O.P	SCRAF	P / REUSAB	LE
=======================================	.======		======	=========	=====	======:	=======	======	======
ACTIVIT	Y	HOURS		STARTING TI	ME		CTIVITY		HOUR
DRILLING:						SAMPLING):		
SAFETY MEETINGS	3 :					W.O. SAM	PLERS:		
BAIL HOLE:	-					LOGGING:			_
SERVICE RIG:						W.O. LOG	GERS:		
W.O. FUEL/SERVI	CE:					DECON E	QUIP.		
W.O. SITE SAFETY	OFFICER					DECON CS	SG.		
W.O. GEOLOGIST:						STEAM CL	EANING:		
W.O. HPT:						W.O. WATE	ER:		
LOST TIME Q.A.						W.O. TOOL	.S / MATERI	AL:	
W.O. DIRECTION:						W.O. SAFE	TY EQUIP:		
MECH. BREAKDOW	1 :					OTHER:			
W.O. MAN HAUL:				ENDING TIM	E	OTHER:		<u> </u>	
OTHER:			-			TOTAL SH	FT HOURS	(8)(10):	
CSG	SIZE F	EEI E	===== <u> OURS</u>			<u>CS</u>	G. SIZE	FEEI	HOUR
RUN:					B. PUL	.L:		<u> </u>	
RUN:		_			B. PUL	.L:			
RUN:					B. PUL	.L:			
RUN S.S.					B. PUL	L:			
нера Нера	DEMIST	emema: ER	FTG	: E	HEPA	DI	EMISTER		FTG
				<u> </u>		_			
		_				_		_	
						_		_	<u> </u>
COMMENTS			=====			======	222222	=======	=====
				······································	APPROV	AL	·		

TYPICAL GEOLOGRAPH STRIP CHART



WHC-SD-EN-TP-009, Rev. 0

		•••	_		21.51.00		Boring or W	Vell Na.			
				OREHU	OLE LOG		She	eet of			
Locati	ion _		_,,	***************************************		Project	···				
Elevat	tion					Drilling Contractor					
Drillei	r					Drilling Method and	Equipment				
l .											
·			(Sign/Print	Name)			(Sign/Print	Date n/Print Name)			
Depth		Sar	nple			e Description		Comments			
	ر	Type and No.	Blows or Recovery	Graphic Log	Soil Classification, Par Moisture Content, Son Reac	ticle Size Distribution ting, Angularity, Mine tion to HCI.	, Color, raiogy,	Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level			
	_	į					·				
	\dashv				<u> </u>		·				
	ᅥ										
**************************************		}						-			
/-	_				· · · · · · · · · · · · · · · · · · ·						
<u>.</u>	\dashv										
(ICC)	\dashv										
,											
••קר											
>	\dashv			!							
خ ر	ㅓ										
••	\dashv										
***	-			}							
¥	\dashv										
,	\Box			. [
	\rightarrow										
	-		i	Ì							
_			}								
•			Ì		 						
	-]	}			<u>.</u>				
	-	İ	ł	ţ							
_				Ţ							
-				[
	-		Ī	[
	\dashv			}							
_				į							
-				[
	\dashv			-							
	\dashv	ļ		}							
	\dashv	- 1		ł							

1-4

A-6000-382 (04/90)

	WELL	DEVELOPMEN	IT FORM		Page	of
Well Designation			Weil De	pth		
Screened Interval			Date W	ell Development	is Performed	
BAILING					•	
Water Level Prior	to Bailing		Time of	Measurement		
Volume of Bailer		Numbe	er of Bails Rem	oved	Gallor	15
Summary Descript	tion of Water	Removed				
Water Level After	Bailing	<u>, , , , , , , , , , , , , , , , , , , </u>	Time of	Measurement		
SURGE BLOCK						
Type of Surge Bloc	:k		Dimensi	on of Surge Block		
TD BEFORE	STROKE LENGTH	STROKE FREQUENCY	SURGE INTERVAL	SURGE TIME	TO AFTER	TO DIFFERENCE
4W-2W-1						
						,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
AIRUFT						
Depth of Eductor P	Pipe			Airlift Star	t Time	
low Rate	Ac	cumulated Flow		Airlift Stop	Time	······································
urbidity						
	r		······································			
MECHANICAL PUM	IPING					
umping Techniqu	e	Pump Depth		Pump St	art Time	
low Rate		Accumulated	Flow	Pump St	op Time	
urbidity						

omments		<u></u>				<u></u>
	······································					
	· · ·					
ignature of Pecor	der	Sign and Print		Date	•	

A-6000-393 (03-90)

Z. Generaliza

10

	MHC-20-FI	<u>1-11-003,</u>	IVEN. O	·	
				Boring or Well No.	
WELL SU	JMMARY SHEET			Sheet of	
Location		Project			
			,	ripment	
(Sign/Print Name)			(\$	ign/Print Name)	
CONSTRUCTION DA	TA	Depth		GEOLOGIC/HYDROLOGIC DATA	
Description	Diagram	Feet	Graphic Log	Lithologic Description	
		:[
		<u> </u> -	† †		
and the state of t		<u>:</u> -	}		
		; - -	_		
		<u>:</u>			
		<u> </u>			***
_ +		:[
<u> </u>		<u> </u>	1		
		;	1 1		
***************************************		<u> </u>	}		
		<u> </u> -	ļ ļ		
(3)	1	; ; ; -]		
dif.		<u> </u>] [
		i !			
· n]		
	-	-	1		
		: 	1		
****			}		
N		· -	-		
		i	-		
<u> </u>		-			
		!			
	4	i			
		1	1 1		
		;├ -		- And the state of	
		' ⊢ −	-		
		<u> </u>	-		
		: <u>L</u> _			
		1			
		i [""			
		-	-		
		· 			
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	A-6			
		<u> </u>		Δ 6000-3	84 (04,30)

WHC-SD-EN-TP-009, Rev. 0

WELL CONS	TRUCTION R	EPORT		Page <u>1</u>	of2
Specification No R		Well No			
Project		Casing Elev			
Location		Drifti	ng Method		
Drilling Company		Verification Method			
Ordler		Criteria			
Other (Companies)				Initials	Date
Geologist(s)		Rotary Air Mud Cable Tool D H			<u></u>
		Drilling Fluid			
	•	Other			
Geophysical Logging		Completion Data		quifer Testi	•
Sondes Interval Date Cleaning Cleaning Verification Method Initials Drilling Tools/Rig Temporary Materials	Completed De Date Started Date Complete Static Water Le Comple	evel/Date Control Results Material Strate Control Results Control Results Material Strategy	Type Flow Meter I D Cal Due Date Length of Test Volume Pumpo Drawdown Date of Test Storage/Packin nitials	ed	
Permanent Materials Screen Type Length	Slot Size	Verification Method CriteriaIdentify Additives	lnit	ials	Date
Depth(s)		Lubricants Straig Verification Method	htness Test	<u></u>	,
Criteria		Criteria			
Initials Date		Initials		Date	

WHC-SD-EN-TP-009, Rev. 0

	ONSTRUCTION I continuation sheet			Page <u>2</u> of <u>2</u>
Casing (permanent) Type Size	Placement _	Verification Method	Well Protection	
			Initials	Date
		Protective Posts Protective Casing		
Verification Method		Site Restored		
Criteria		Cap, Hasp and Lock Surface Pad		
		eal/Filter Pack		
Verification Method		•		
Туре	Interval	Volume	Initials	Date
Well Survey/Labeling			Pump Installation	
Verification Method		Verification Method		······································
Criteria		Criteria	<u></u>	
Initials Measurement Point/Surveyed	Date	Pump Decon/Prep	Initials -	Date
Protective Casing/Brass Cap Surveyed		Installed		
Well Number Stenciled	····	Pump Tested		·
Brass Cap Labeled				
		al if performed)		•
Well Abandonment Well Development	Downhole TV Insp	ectionCom	plete As-Built Diagram, Dri	ller's/Geologist's Logs
Comments/Remarks				
				····
				· · · · · · · · · · · · · · · · · · ·
				·

A-6000-436 (09/90)

APPENDIX B

SAFETY ANALYSIS DOCUMENTATION REQUIREMENTS FOR THE DRILL CUTTING CONTAINMENT SYSTEM TEST

រោ

*......

All Parkers

N

N

O

9

THIS PAGE INTENTIONALLY LEFT BLANK

From:

Facility Systems Safety Analysis

33560-89-011

Phone: Date: 3-2073 R3-02 July 24, 1989

Subject:

SAFETY ANALYSIS DOCUMENTATION REQUIREMENTS FOR THE DRILL CUTTING

CONTAINMENT SYSTEM TEST

To:

D. R. Myers H4-54

CC: D. R. Ellingson R3-08
G. L. Kasza H4-56
J. V. Mohatt S0-03
K. J. Moss & Come R3-08
L. D. Muhlestein N1-31
D. D. Stepnewski N1-31
FSSA File/LB

The scope of this letter is limited to design and cold testing in uncontaminated soil.

Activities which represent hazards routinely encountered and accepted by the public are exempt from the requirements for safety analysis defined by WHC-CM-4-46, Nonreactor Facility Safety Analysis Manual. The proposed Drill Cutting Containment System described in the attached safety assessment falls into the exempt category because of the following three characteristics:

- I. The activity has no potential to introduce additional hazardous material into the environment. The containment system will control and provide containment of contaminants that may already be present in the soil or water where the well is drilled. The system is designed to provide containment of potentially contaminated soils or water as groundwater monitoring or vadose zone wells are drilled. The system will not be used in areas of known contamination.
- 2. The containment system will not increase the dispersability of hazardous materials already present in the environment. The system prevents dispersion of potentially contaminated soil or water by capturing the drill cuttings in the waste drum, the sample tube, or the containment tank. The air is discharged through roughing (for dust control) and high efficiency particulate air (for ALARA purposes) filtration.
- 3. The activity does not concentrate or accumulate hazardous material already present in the environment to any significant degree. Any contaminated materials which may be encountered while drilling are captured and contained. The contaminated materials stay at their original concentrations or are mixed with additional drill cuttings.

WHC-SD-EN-TP-009, Rev. 0

D. R. Myers Page 2 July 33560-89-011

Thus, this activity can be said to represent hazards routinely encountered and accepted by the public, and as such is exempt from the safety analysis requirements of WHC-CM-4-46, including the hazard classification process. Standard industrial safety and fire protection requirements, as well as the radiological protection requirements in application throughout the site are still pertinent, however. Safety review in accordance with the assigned Impact Level 2 (an impact level 2 was assigned in anticipation of future use of the system) is also still in force. Any contaminated materials encountered must be sampled, analyzed, and disposed or according to established procedures. Use of this system in areas of known contamination will require reevaluation.

If you have any questions please feel free to call.

J. P. Hinckley, Manager Facility Systems Safety Analysis

iar

N

O

Attachment

Concurrences:

A. R. Schade, Manager NFS

R. J. Landon, Manager Regulatory Analysis

33560-89-011 Attachment Page 1 of 5

TECHNICAL ASSESSMENT OF THE DRILL CUTTINGS CONTAINMENT SYSTEM

The Environmental Engineering and Technology Function is required to provide the environmental and safety evaluation of the proposed Cuttings Containment System test activity prior to start of the test. The test will involve construction of a groundwater monitoring well utilizing a Dual Wall Percussion Hammer (DWPH) drilling rig in conjunction with the Cuttings Containment System. This technical assessment is intended to address the following concerns:

- 1. Is there any potential to introduce additional hazardous or radiological material presently in the environment?
- 2. Will the proposed action increase the dispersability of any hazardous or radiological material presently in the environment?
- 3. Will the proposed activity concentrate or accumulate significant quantities or radiological or hazardous materials?

The following discussion to addresses these concerns.

CUTTINGS CONTAINMENT SYSTEM

* 6*4

7.1

N

Since the act of drilling does not create contamination but instead allows for access to potentially contaminated earth materials, the Cuttings Containment System will provide a means of preventing the dispersion of contamination during the drilling of boreholes. Dispersion is prevented by removing all drill hole cuttings from the hole-cleaning airstream before the air is released to the environment through a combination of mechanical devices. During drilling, the airstream picks up the cuttings at the bottom of the borehole and transports them to the surface through the dual wall drill pipe. At the surface, the cuttings-laden airstream is conducted through a flexible rubber hose to the cyclone separator. In the cyclone, the coarse cuttings are separated by centrifugal action and fall by gravity into sealed 55 gallon drums. A smaller sampling cyclone, located on the wall of the cyclone separator captures a fraction of the cuttings and directs them into a closed sample tube for later geologic sampling and logging. The airstream, after it passes out of the cyclones, still contains some dust-size particulates. It is next conducted by rubber hose to the cuttings containment unit where the remaining fines settle out and are removed by velocity drop or are captured in either the roughing filter or the HEPA filter. The Cuttings Containment System is totally enclosed and all cuttings are containerized for appropriate disposal.

33560-89-011 Attachment Page 2 of 5

TEST LOCATION

The location selected for the construction of the test groundwater monitoring well (W 19-30) is in the Hanford 200 West Area, across 16th Street from the Uranium Oxide Plant (Figure 1). The well is in the area between the 216-U-1/2 and 216-U-17 cribs and is part of a project to construct three groundwater monitoring wells to determine the water quality between these cribs. Two wells for the project have recently been completed using cable tool drilling rigs. Both of these wells are on the other side of 16th Street, some 200 feet north of the selected location.

The first well, W 19-28 encountered minor radioactive contamination (up to 400 counts per minute) over a 7 foot interval (35-42 feet below ground surface). The well was completed to 215 feet deep with no other evidence of contamination. The source of this shallow contamination is thought to be the buried pipeline between U-Plant and 216-U-8 crib.

The second well, W 19-29 was located 200 feet east of W 19-28 (down gradient of the groundwater table) and was completed to approximately 217 feet deep without encountering any radioactive contamination.

The location selected for the test well is expected to have very low potential for either radioactive or hazardous waste contamination since the site is down-gradient from any known contaminated areas and is located far from any potential sources of contamination. A discussion of the site conditions is included in the Operational Groundwater Monitoring Plan, WHC-SD-EN-AP-007.

TEST PROCEDURE

As previously stated, the primary purpose of the test is to determine the effectiveness of the Cuttings Containment System in preventing the introduction of potentially contaminated drill cuttings into the above ground environment during the drilling of groundwater monitoring wells. This test will also provide the opportunity to determine the efficiency of the DWPH drilling method in the Hanford geologic environment. The Cuttings Containment System is adaptable to any of the commercial air-bailing drilling techniques and the use of the selected drilling method will not bias the test results.

The Cuttings Containment System test will be controlled by an approved test plan and will be supervised by the cognizant engineer and the project geologist. As is standard procedure for all drilling operations, the work will be monitored by both a radiation protection technician (RPT) and a representative of Environmental Field Services (Site Safety Officer). Additional monitoring may be requested of Hanford Environmental Health Foundation.

92 - 2 - 7 4 3 - 7 -

During drilling, engineered barriers are provided by equipment design to prevent the introduction of contamination into the above ground environment. These barriers include a completely enclosed drill cuttings removal system consisting of:

- 1. Dual wall drill pipe with threaded couplings
- 2. Heavy gauge rubber hose and specified fittings, valves, and piping
- Totally enclosed cyclones
- 4. Sealed, heavy gauge plastic sample collectors
- 5. Sealed barrels and connectors for containing coarse cuttings
- 6. Cuttings containment vessel for fine cuttings
- 7. Instrumented roughing filter and HEPA filter in series.

The design and location of the driller's control console allows for "quick stop" shutdowns of the drilling equipment.

In addition to the above mentioned engineered barriers, the following administrative controls, applied via the test plan, will also aid in mitigating the dispersal of contamination and help satisfy the earlier listed concerns:

- 1. The location of the test well will be initially tested for contamination with a pilot hole drilled by a government-owned hollow-stem auger. The pilot hole will be drilled at least 100 feet deep to assure that no radioactive contamination will be encountered. The test well will be located within 10 feet of the pilot hole. The test well will be moved if contamination is found at the selected location.
- 2. Before the start of drilling and at regular intervals the entire Cuttings Containment System will be leak tested with Dioctyl Phthalate (DOP) to assure that there are no leaks in the system and that the HEPA filter is operating as required. All leaks will be sealed before drilling will proceed.
- 3. The drill cuttings received in the sampling tube will be monitored continuously to determine if radioactive contamination is encountered. The RPT will notify the driller to stop drilling if contamination is encountered.

33560-89-011 Attachment Page 4 of 5

- 4. Direct reading instruments will be used during the entire test. The monitoring will involve area-wide as well as point monitoring as dictated by the test plan. A procedure for immediate shutdown by alternate (other than verbal) methods will be instituted. Any member of the test team will be authorized to initiate shutdown in the event that any monitoring or other indication deems it necessary. The types of indicators which will prompt a shutdown include the following:
 - o rapid change in pressure gauge readings.
 - o visual or acoustic indications
 - any reading 3ppm above background on any organic vapor monitoring instrument
 - o any reading above background on radiological survey instruments
 - o any noticeable leaking in Cuttings Containment System.

The above listed engineering barriers and administrative controls will, if implemented properly, provide the necessary safeguards to prevent significant release to the environment or to mitigate any concentration of material in the Cuttings Containment System.

RESPONSE TO CONCERNS

San San

9 ° E

V

The following is a point-by-point response to the concerns voiced by the Radiation Safety organization:

1. Is there any potential to introduce additional hazardous or radioactive material into the environment?

Response: There is no potential to introduce additional contaminants into the environment under the planned test sequence. If any contaminants are located in the immediate vicinity of the test well, they will very likely be determined in the initial auger pilot hole. In the unlikely event that the contamination was missed in the pilot hole and it is encountered approximately 10 feet down-gradient, the already leak-tested Cuttings Containment System should capture any materials prior to shutdown of the drill rig.

2. Will the proposed action increase the dispersability of any hazardous or radioactive material presently in the environment?

33560-89-011 Attachment Page 5 of 5

Response: Constructing a groundwater monitoring well with a drill rig using the Cuttings Containment System will not increase the dispersability of contaminants since all drill cuttings are contained within a totally enclosed and continuously monitored equipment system. The purpose for conducting the test activity is to verify that the Cuttings Containment System operates as intended. The selected test location will have a minimal chance of being contaminated since a pilot hole will be used to assure that there is no detectable contamination at that location.

3. Will the proposed activity concentrate or accumulate significant quantities of radiological or hazardous materials?

Response: Any contaminated materials encountered during drilling will be captured in the Cuttings Containment System and will remain in the original concentration of the material or will be diluted by the other earth materials in the containers. However, as stated previously, contamination is not expected since a pilot hole will examine the area before the borehole is drilled.

CONCLUSION

3

حققك

* #3

N

S CA With the application of the controls stated in the test plan, the risk of exposure to contamination during the drilling of the test well is minimized to what should be an acceptable level. In the event that contamination is encountered during the pilot hole drilling, the worst case would involve contaminating one or two government owned auger flights. No other equipment or personnel should be contaminated. The test location would then be moved to a different site with no detectable contamination.

This page intentionally left blank.

error V

(N

N

0

APPENDIX C SAFETY DOCUMENTATION FOR THE ODEX DRILLING METHOD TEST

in

(......

ptroque.

'.O

9 2

THIS PAGE INTENTIONALLY LEFT BLANK

S

(C)

-

N

% 6



Internal Memo

From:

Geosciences Group

81230-92-007

Phone: Date: 6-0940 H4-56 March 6, 1992

Subject:

SAFETY DOCUMENTATION FOR THE ODEX DRILLING METHOD TEST

To:

к. и). L	i Ch	field	L5-57
cc:	J.	Ε.	Auten	H5-29
	D.	0.	Hess	L6-57
	G.	L.	Kasza	H5-29
	D.	R.	Myers	H4-14
			Takasumi	L4-78

KRF:GLK File/LB

INTRODUCTION

The proposed test of the Odex Drilling Method at Hanford will consist of drilling, installing and completing three groundwater monitoring wells using a commercially available Odex down-hole hammer on a commercially available air-rotary drill rig. Appropriate productivity, quality and safety related criteria will be monitored, measured and documented during the work. This data will be evaluated to determine if the Odex method will satisfy existing safety requirements and RCRA program data quality objectives, and be a cost effective alternative to the Cable Tool Drilling Method.

EQUIPMENT

9

14 3071 (18)

The drilling equipment to be tested is a commercially available Odex downhole hammer that will be mounted on the drill pipe of a standard air bailed rotary drilling rig. This hammer provides the force to disaggregate, fracture, and pulverize the earth media to be penetrated and to advance the temporary well casing. Compressed air from a rig-mounted air compressor is used to power the hammer and expel the cuttings from the hole. Concentric dual string drill pipe is used to get the compressed air to the hammer and conduct the cuttings from the hole. The drill rig and all ancillary equipment will be commercially available and standard to the water well drilling industry.

While drilling, the cuttings travel in the compressed air stream up the casing and out through the diverter. The standard well drilling industry practice is that the drill cuttings enter a cyclone separator where the air velocity is reduced and coarse cuttings fall out of the air-stream. These cuttings are normally allowed to form an open pile next to the drill rig since they are non-hazardous. In standard practice, the dust size particulates are carried out of the cyclone in the exhaust air stream. Water misting devices are usually used for dust control.

R. D. Lichfield Page 2 March 6, 1992

13

81230-92-007

During the proposed test of the Odex method, the Hanford Drill Cuttings Containment System (DCCS) will be incorporated into the cuttings removal system to capture and contain all drill cuttings. This same DCCS was used and evaluated during the test of the Dual Wall Percussion Hammer Method in 1990 (Appendix 1). The DCCS is comprised of a large cyclone to facilitate separation of the coarse cuttings, 55 Gal. containment drums to hold the coarse cuttings, a smaller cyclone equipped with a sampling tube to capture a fraction of the cuttings for geologic logging and physical sampling, and the cuttings containment box. This containment box employs a drop in air velocity, a rougher/demister filter, and a high efficiency particulate air (HEPA) filter to prevent particulates from entering the atmosphere. The cuttings containment box was built to Nuclear Quality Assurance Level 1 requirements and is qualified as a Low Specific Activity (LSA) component, permitting the containment and transportation of LSA classified material. The HEPA filter will be DOP tested to assure that fine particulates do not escape into the atmosphere.

When the DCCS is employed, cuttings exit the hole in the compressed air stream and travel through the diverter and hose connections into the closed-circuit cyclone separator. In the cyclone, most of the large cuttings fall by gravity into the sealed containment barrels. A small fraction of the coarse material is captured by the sampling cyclone. exhaust airstream and any entrained fines is then discharged through a hose into the containment box. Entering the expansion chamber of the containment box, a velocity drop occurs which enhances the settling of the fines. The low velocity airstream sequentially passes through the demister/rougher filter and then the HEPA filter before entering the atmosphere. The cyclone separator and sealed containment barrels of the DCCS efficiently capture and contain any formation water that is produced along with the cuttings when drilling below the water table. Water vapor that is entrained in the air-stream coalesces on the rougher/demister filter and is then held in the containment box. The integrity of all components comprising the DCCS will be verified by DOP testing before any hole will be drilled. The effectiveness of the DCCS for preventing the spread of potential contaminants was confirmed in the Dual Wall Percussion Tests (Appendix 1).

TEST WELL LOCATIONS

As mentioned earlier, three sites are proposed for drilling groundwater monitoring wells with the Odex and DCCS equipped drill rig; two sites are on the northern boundary of the 200 West Area at the Waste Management Area 5 and the remaining site is located south of the Grout Facility which is located east of the 200 East Area. Experienced geologic staff from the WHC Geosciences Group have examined the drilling logs and well completion reports for the closest nearby wells and have determined that no radioactive or chemical hazards were detected during the drilling at any of those sites. Due to the fact that no radioactive materials have been

R. D. Lichfield Page 3 March 6, 1992 81230-92-007

disposed near those sites and this investigation of the adjacent well drilling history, there is very little chance to encounter radioactive or hazardous contamination at the proposed well locations.

The first two wells, 299-W6-11 and 299-W6-12, will be drilled at the Waste Management Area 5 RCRA Facility (Figure 1). Waste Management Area 5 is characterized as a "Future Burial Ground" and as such, no waste has yet been disposed to the facility. The logs and drilling reports from wells (299-) W6-8, W6-7, and W7-8 were examined by an experienced geologist who has determined that no radiation hazard was experienced in any of the adjacent drillholes. The proposed locations are on the fringe of the 200 West Area Carbon Tetrachloride plume and very low traces of carbon tetrachloride have been recognized in the groundwater by laboratory instrumentation. None has ever been detected by the field screening instruments in the breathing zone while drilling or while handling the well development water. It would be extremely unlikely that any Carbon Tet would be recognized during the drilling operations since the large volume of compressed air sent down the hole to power the drilling hammer would effectively dilute and disperse the potential contaminant to below detectable limits.

The remaining well will be drilled at location 299-E25-44 on the south boundary of the Grout Treatment Facility (Figure 2). No radioactive or hazardous contaminants have yet been disposed at Grout. Logs from the drilling of wells 299-E25-27, 299-E25-38, 299-E25-39, and 299-E26-33 have been examined by an experienced geologist and no record of the detection of radioactive or chemical contamination was noted.

CONDUCT OF TEST

9

As a minimum, all safety, health, and contamination control requirements that are applicable to the current RCRA drilling program will be applied to the Odex test activities. Requirements include 40 Hr hazardous waste worker training for all operator and test personnel, onsite surveillance by a Health and Safety Officer, and radiation monitoring by a Health Physics Technician.

Additional safeguards will include the already described Drill Cuttings Containment System whose containment ability will be verified by tracer testing before starting each drill hole, experienced contractor drilling personnel, and an approved test plan which will allow any of the test personnel to stop the test at any time.

SAFETY DOCUMENTATION

The following issues relating to safety documentation have been reviewed and addressed: (1) compliance to DOE Order 5481.1B, (2) Operational Readiness Review, and (3) compliance to DOE Order 5480.19.

R. D. Lichfield Page 4 March 6, 1992 81230-92-007

1 - Compliance to DOE Order 5481.18

A Safety Analysis was issued for the drilling of three boreholes using the DCCS and is attached as Appendix 2. It was determined that the consequences of the drilling activities were well within the radiological risk acceptance guidelines of 0.1 rem offsite dose equivalent and 0.5 rem onsite dose equivalent. The scope of work is similar in that all well sites were located in uncontaminated areas and that the DCCS was used to contain all cuttings generated in the drilling operation.

The potential for radioactive contamination does exist. Exposure will be minimized through several approaches. First, the test activities will be conducted in areas that are known to have a minimal chance for containing contamination. Second, the Drill Cuttings Containment System is a proven approach to preventing the spread of contamination due to a tested filter system. In addition, Monitoring by the Health Physics Technician will detect any contamination as soon as it is brought to the surface. If radioactive contamination is noted, drilling will be suspended. This will limit the amount of radioactive material brought to the surface and thereby limit exposure. A Job Safety Analysis and a Radiation Work Permit will be in place for this activity.

<u> 2 - Operational Readiness Review</u>

0

The following items discuss readiness of personnel, procedures, and equipment.

Personnel: All field personnel are trained to the 40 hr Hazardous Waste Worker requirements and radiation worker specifications. All Personnel are required to read the JSA and the Radiation Work Permit (RWP) prior to field activities. A pre-job safety meeting will be conducted and documented.

Procedures: The test will work to the protocol of WHC-CM-7-7, Environmental Investigations and Site Characterization Manual, especially EII 6.7, Resource Protection Well and Test Borehole Drilling. The work will be performed with an approved work package.

Equipment: Equipment used will be in a safe condition, receive routine maintenance and inspections, and will be operated by personnel who are trained in its use and have used the same equipment in the past to perform similar work.

R. D. Lichfield Page 5 March 6, 1992 81230-92-007

3 - Compliance to DOE Order 5480.19

The intent of this order will be met through use of WHC-CM-7-7 procedures and other documents such as test and sampling plans, Letters of Instruction, Statements of Work, etc.

Contact Mr. G. L. Kasza at 376-0763 for further information or if there are any questions.

Recent

K. R. Fecht, Manager Geosciences Group

dyl

Environmental Safety Assurance has evaluated this memo and concludes that the safety documentation for the described work meets the intent of the WHC and DOE criteria. Other than the potential for radioactive materials to be involved, the hazards of well drilling are routinely encountered and accepted by the public. A RWP and the limited potential to encounter radioactive material in addition to the use of the Drill Cuttings Containment System for capture of all cuttings generated in the drilling operation provide worker protection and also provide adequate protection of the non-involved onsite personnel and the public.

CONCURRANCE

O

R. D. LichfieTd / V Environmental Safety Assurance

Date 3/6/92

This page intentionally left blank.

Ç.

⊘

APPENDIX D ODEX DEMONSTRATION SCHEDULE

3

N

0

THIS PAGE INTENTIONALLY LEFT BLANK

N

O

ODEX DEMONSTRATION SCHEDULE 2/3/92

)	Activities	Start Date Finish Date			Mar '92						Apr '92					May '92			
		Start Date	Tansii Dale	24	2	9	16	23	30	6	13	20	27	4	11	18			
	WELL NO. 299-W6-12					<u> </u>													
	LLBG Well No.1 (Mob/Setup)	3/9/92	3/10/92																
	LLBG Well No.1 (Shake Down)	3/10/92	3/12/92																
	LLBG Wello No. 1 (Drl)	3/13/92	3/25/92																
	LLBG Well No. 1 (Demob)	3/25/92	3/26/92																
	LLBG Well No. 1 (Bpull/Run SS)	3/27/92	4/1/92																
	LLBG Well No. 1 (Dev/P&Post)	4/2/92	4/3/92																
										-									
	WELL NO. 299-W6-11																		
	Service Rig and Equip.	3/26/92	3/29/92				•												
ស	LLBG Well No. 2 (Mob/Setup)	4/1/92	4/2/92						-										
മ	LLBG Well No. 2 (Shake Down)	4/3/92	4/4/92						1										
E. 2	LLBG Wello No. 2 (Drl)	4/5/92	4/15/92	į į					ı										
-	LLBG Well No. 2 (Demob)	4/15/92	4/16/92																
೧	LLBG Well No. 2 (Bpull/Run SS)	4/17/92	4/22/92								Ę	_							
4	LLBG Well No. 2 (Dev/P&Post)	4/23/92	4/24/92																
7																			
r jerry	WELL NO. 299-E25-44										\neg								
N	Service Rig and Equip.	4/17/92	4/18/92																
	GTF Well No. 1 (Mob/Setup)	4/19/92	4/22/92																
÷	GTF Well No. 1 (Shake Down)	4/23/92	4/24/92																
0	GTF Well No. 1 (Drl)	4/25/92	5/2/92			\neg													
	GTF Well No. 1 (Demob)	5/3/92	5/6/92																
	GFT Well No. 1 (Bpuil/Run SS)	5/7/92	5/10/92																
	GFT Well No. 1 (Dev/P&Post)	5/13/92	5/14/92												п				
													\exists			一			
	FINAL REPORT	4/5/92	5/22/92			寸				ologge/15	Make:	unico b	pondiše	10/41%	0.000				
				1	\neg			$\neg \dagger$	_		_	\dashv	_			\dashv			
					1	\dashv	7	\dashv	\top	\dashv	\dashv	7	\dashv			一			
					7	\dashv		+	1	\exists		\dashv	\dashv	一	\dashv	\dashv			
				\dashv			\dashv	_	1	+	7	\dashv	\dashv		-	一			
Ī								\top		7	\dashv	_	+	+	<u> </u>	\dashv			
_								Щ.	— —					[<u> </u>				

THIS PAGE INTENTIONALLY LEFT BLANK